

ADDENDUM NO. 2

March 12, 2019

Engineer:

Parametrix
1019 39th Avenue SE
Suite 100
Puyallup, Washington 98374

Owner:

The Tulalip Tribes
8802 27th Avenue NE
Tulalip, WA 98271-9694

**4TH STREET SEWER EXTENSION TO MBR PLANT
BID SOLICITATION NO. 019-002**

To: All Holders of the Bidding Documents, Contract Specifications, and Construction Drawings

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents, Contract Specifications, and Construction Drawings for the opening date of March 14, 2019.

Acknowledge receipt of this addendum on the Bid Proposal Form. Failure to do so may subject the Bidder to disqualification. This addendum consists of:

5 Pages of text (including this cover sheet)



3/12/2019

Prepared by: _____
John L. Wright III, P.E.

Checked by: _____
Austin R. Fisher, P.E.

Approved by: _____
Happy Longfellow, P.E.

ADDENDUM NO. 2

4TH STREET SEWER EXTENSION TO MBR PLANT BID SOLICITATION NO. 019-002

REVISIONS TO CONTRACT DOCUMENTS

DIVISION 0 – BIDDING REQUIREMENTS, CONTRACT FORMS, AND CONDITIONS OF CONTRACT

1. Notice to Bidders

- a. The bid opening date on page NTB-1 is revised to read “March 21, 2019.”

2. Bid Proposal Form

- a. The Schedule of Prices, pages BPF-3 and BPF-4, are replaced in their entirety with the replacement Schedule of Prices labeled Addendum No. 2. Revisions include modified quantities for Bid Items 46 and 47 as well as the addition of Bid Items 22 and 42.

CONTRACT PLANS

- 1. Add the attached new plan sheet numbered SS6.

QUESTIONS AND ANSWERS

- 1. **Question: WSDOT section 9-05.4 describes coatings for corrugated metal culvert pipe. No ductile fabricators we currently deal with have ever applied this to ductile iron pipe nor have the ability to. Can we use a standard shop applied primer or coal tar epoxy in lieu of this CMP treatment?**

Answer: A standard coal tar epoxy meeting the requirements of AWWA C151 shall be used for the ductile iron pipe.

BID SCHEDULE

TULALIP TRIBES



4TH STREET SEWER EXTENSION TO MBR PLANT PROJECT

SCHEDULE OF PRICES

(Work Within Tribal Reservation Boundary
Washington State Sales Tax Does Not Apply)

UTILITY IMPROVEMENTS						
ITEM NO.	SECTION	ITEM DESCRIPTION	UNIT	APPROX. QTY.	UNIT PRICE DOLLAR CENTS	AMOUNT DOLLAR CENTS
1	1-04	MINOR CHANGE	FA	1	\$25,000	\$25,000
2	1-05	UTILITY SURVEYING	LS	1	\$	\$
3	1-05	RECORD DRAWINGS (MINIMUM BID \$2,000)	LS	1	\$	\$
4	1-07	SPCC PLAN	LS	1	\$	\$
5	1-09	MOBILIZATION	LS	1	\$	\$
6	1-10	PROJECT TEMPORARY TRAFFIC CONTROL	LS	1	\$	\$
7	2-01	CLEARING AND GRUBBING	LS	1	\$	\$
8	2-02	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	1	\$	\$
9	2-02	REMOVING ASPHALT CONC. PAVEMENT	SY	300	\$	\$
10	2-02	REMOVING CEMENT CONC. SIDEWALK	SY	20	\$	\$
11	2-02	REMOVING CEMENT CONC. CURB AND GUTTER	LF	30	\$	\$
12	2-02	POTHOLE EXISTING UTILITY	EACH	10	\$	\$
13	2-09	RESOLUTION OF UTILITY CONFLICTS	FA	1	\$50,000	\$50,000
14	2-09	DEWATERING	LS	1	\$	\$
15	2-09	CONTROLLED DENSITY FILL	CY	10	\$	\$
16	4-04	CRUSHED SURFACING TOP COURSE	TON	60	\$	\$
17	4-04	CRUSHED SURFACING BASE COURSE	TON	110	\$	\$
18	5-04	HMA CL. 1/2 IN. PG 64-22	TON	80	\$	\$
19	5-04	TEMPORARY ASPHALT RESTORATION HMA CL. 1/2 IN. PG 64-22	TON	30	\$	\$
20	6-02	PIPE SUPPORT FOR DUCTILE IRON FORCE MAIN AT BRIDGE CROSSING	LS	1	\$	\$
21	7-05	CHANNEL EXISTING SANITARY SEWER MANHOLE, COMPLETE	EACH	2	\$	\$
22	7-05	MANHOLE 48 IN. DIAM. TYPE 1	EACH	1	\$	\$
23	7-05	INTERIOR PROTECTIVE COATING EXISTING SANITARY SEWER MANHOLE, COMPLETE	EACH	1	\$	\$
24	7-08	EXTRA EXCAVATION	CY	100	\$	\$

UTILITY IMPROVEMENTS						
ITEM NO.	SECTION	ITEM DESCRIPTION	UNIT	APPROX. QTY.	UNIT PRICE DOLLAR CENTS	AMOUNT DOLLAR CENTS
25	7-08	FOUNDATION MATERIAL	TON	200	\$	\$
26	7-08	SHORING OR EXTRA EXCAVATION CLASS B	LS	1	\$	\$
27	7-08	16 IN. DIAM. STEEL CASING (OPEN CUT)	LF	20	\$	\$
28	7-08	20 IN. DIAM. STEEL CASING (OPEN CUT)	LF	40	\$	\$
29	7-09	DUCTILE IRON PIPE FOR FORCE MAIN 8 IN. DIAM.	LF	950	\$	\$
30	7-09	DUCTILE IRON PIPE FOR FORCE MAIN 10 IN. DIAM.	LF	70	\$	\$
31	7-09	PVC C900 PIPE FOR SANITARY SEWER FORCE MAIN 8 IN. DIAM	LF	650	\$	\$
32	7-09	PVC C900 PIPE FOR SANITARY SEWER FORCE MAIN 10 IN. DIAM.	LF	250	\$	\$
33	7-09	PVC PIPE DRAIN 3 IN. DIAM.	LF	20	\$	\$
34	7-09	10 IN. FORCE MAIN DROP INLET, COMPLETE	LS	1	\$	\$
35	7-09	8 IN. FORCE MAIN DROP INLET, COMPLETE	LS	1	\$	\$
36	7-12	COMB. AIR RELEASE / AIR VACUUM VALVE ASSEMBLY 3 IN. (SEWER)	EACH	1	\$	\$
37	7-12	VACUUM RELEASE VALVE 3 IN. (SEWER)	EACH	1	\$	\$
38	7-12	10 IN. CONNECTION FORCE MAIN	EACH	2	\$	\$
39	7-12	10 IN. MASTER SEWER METER VAULT INCL. ELECTRICAL CONDUIT PANEL TO METER	EACH	1	\$	\$
40	7-12	8 IN. FLEX-TEND DOUBLE BALL EXPANSION JOINT	EACH	2	\$	\$
41	7-17	PVC SANITARY SEWER PIPE 8 IN. DIAM.	LF	120	\$	\$
42	7-17	PVC SANITARY SEWER PIPE 12 IN. DIAM	LF	80	\$	\$
43	8-01	EROSION/WATER POLLUTION CONTROL	LS	1	\$	\$
44	8-01	SILT FENCE	LF	520	\$	\$
45	8-01	INLET PROTECTION	EACH	4	\$	\$
46	8-02	TOPSOIL TYPE A	SY	650	\$	\$
47	8-02	SEEDING, FERTILIZING AND MULCHING	SY	650	\$	\$
48	8-04	CEMENT CONC. TRAFFIC CURB AND GUTTER	LF	30	\$	\$
49	8-14	CEMENT CONC. SIDEWALK	SY	15	\$	\$
Subtotal:					\$	
TERO (1.75%):						
TOTAL (Including TERO):					\$	



48258
REGISTERED

1019 39TH AVENUE SE, SUITE 100 | PUYALLUP, WA 98374
P 253.604.6600
WWW.PARAMETRIX.COM

THE TULALIP TRIBES

4TH STREET SEWER EXTENSION TO

MBR PLANT

TULALIP, WASHINGTON

SANITARY SEWER MAIN

PLAN AND PROFILE

STA 200+00 TO 202+00

SS6

1 INSTALL NEW 8" PVC (C900) FORCE MAIN.

2 INSTALL NEW 12" PVC (SDR 35) SANITARY SEWER.

3 INSTALL NEW 12"W (DI) WATER MAIN.

4 AIRTIGHT LID

CONSTRUCTION NOTES:

1. CONTRACTOR TO FIELD VERIFY ALL EXISTING UTILITIES.
2. ALL WATER MAIN AND FORCE MAIN JOINTS AND FITTINGS SHALL BE RESTRAINED.
3. ADJUST ALL EXISTING UTILITIES TO FINISH GRADE.
4. THE CONTRACTOR SHALL PROTECT ALL PRIVATE AND PUBLIC UTILITIES FROM DAMAGE WHEN TRENCHING ACROSS OR BESIDE THESE EXISTING UTILITIES.

LEGEND:

HMA CLASS 1/2" PG 64-22

 CEMENT CONCRETE

GRASS